

Supa-Trac™





Light Duty

Description

Supa-Trac is durable and flexible to create a firm surface for walkways, roadways, temporary buildings and structures, even heli-pads or car parks!

The panels can be laid in minutes with no need for specialist tools, saving valuable time and money, and is designed to be 60% lighter than its aluminium counterpart. It's still the quickest temporary floor to install and extract on the market (40m2/hour per man).

Guide price

£62.75 (excl. VAT)

*We advise checking any agreed or pre-authorised disclaimers on our website before installing or using any of our products, along with live updated and discounted prices available.

- ✓ Compresses surfaces to provide a stable area
- ✓ Product compatibility to satisfy any path/roadway application
- ✓ Easy to clean, transport and store with extensive lifespan
- ✓ Resistant to UV damage, solvents and is non-corroding













Specifications

Size	Panel: 966mm [L] x 275mm [W] x 27mm [H] Sheet: 0.21m2
Weight	6Kg
<u> </u>	20 tonnes
Surface	Non-slip surface
Material	Polypropylene Copolymer (PPCP)
Colour	Grey as standard. Other colours available (subject to minimum order quantities)

The Supa-Trac panels can support further weights and vehicles with up to 20 tonnes (depending on ground conditions), plus far greater static weights.

It's the widest used temporary flooring system by the military and has shown the range of benefits it can offer, with its high load capacity and resistance in extreme weather conditions, whilst allowing light, air and water to the ground below,



Contact us to find out about products available for hire and finance.

Step 1

Step 2

Step 3

Step 4









Download MultiMatts Brochure

How to install the Supa-Trac



Preparation

Supa-Trac can be deployed over most surfaces without any ground preparation. A protective membrane is optional.



Installation

There is no requirement for specialist skills or tools. Supa-Trac comes in sections for ease of use and to install. Start by laying from the top corner and work down in rows and then across until the area is complete.



Connection

Press the integrated security pins from one tile onto the next. Supa-Trac ramps may be required to prevent any trip hazards.













